BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18318/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Improvements to drains in 1st to 4th main road, 2nd cross road to 8th cross road in tatanagara in ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Narasimhaiah N		
				In Figures		In Words
1	20	Hire charges of 100 KVA generator including operator, fuel, transportation and handling charges	Hour	600.0	12000.00	Rupees Six Hundred Only
2	616.5	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH	Cum	80.0	49320.00	Rupees Eighty Only
3	6781.5	Removing B.S Slab of Drain and stacking including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	60.0	406890.00	Rupees Sixty Only
4	513.75	Construction of embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300-2 complete as per specifications which includes watering charges and compaction	Cum	310.0	159262.50	Rupees Three Hundred Ten Only
5	5764.27	Refixing stone slabs of drains and pointing in C.M (1:3) including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	70.0	403498.90	Rupees Seventy Only
6	1017.23	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (10.0 cms thick)	Sqm	770.0	783267.10	Rupees Seven Hundred Seventy Only
7	524.02	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	Cum	68.62	35958.25	Rupees Sixty Eight and Sixty Two Paise Only
					1850196.75	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92